

भिवंडी निजामपूर शहर महागनरपालिका, भिवंडी.
बांधकाम विभाग.



शुध्दीपत्रक

कामाचे नाव:- प्र.क्र.४५ कामतघर सर्वे नं.१५८ पै.सर्वे नं.७१, ७२ व ७३ या परिसरांत
मंजुर विकास आराखडयातून रस्ते विकसीत करणे.

विषय :- ई-निविदा सुचना क्र.४६ सन २०१८ मधील शुध्दीपत्रक

ई-निविदा सुचना क्रमांक ४६ सन २०१८-१९ मध्ये अनुक्रमांक ४ मधील इसान्याची
रक्कम रु.३,००,०००/- नजरचुकीने टंकीत झाली असून त्याजागी रक्कम रु.१,५०,०००/- वाचावे.

तसेच वरील विषयांकित कामाचा नजरचुकीने बी-२ फॉर्म ऐवजी बी-१ फॉर्म बनविण्यात
आला आहे. तरी सदर कामाचा बी-२ फॉर्म दुरुस्त करण्यांत आला आहे.

XXXX

शहर अभियंता

भिवंडी नि.शहर महानगरपालिका.

**NAME OF WORK :- CONSTRUCTION OF D.P.ROAD AT KAMATGHAR SERVEY
NO.158,71, 72,73 AT KAMATGHAR IN WARD NO.45.**

ABSTRACT

Quantity	Unit	Item no.	Description	Rate	Amount
42984.00	Cmt	1	Providing earth work in embankment with approved materials obtained form private land including all lifts and 50m lead laying in layers of 20 to 30 cm thickness breaking clods dressing to the required lines curves grade and section watering and compaction to 955 of standard proctor density with vibratory roller etc complete.		
840.00	Cmt	2	Supplying 15 to 23cm Trap/granite/ quartzite /gneiss/laterite stone rubble at the road side for soling/metal including conveying & stacking etc complete.		
840.00	Cmt	3	Laying 15 to 23cm Trap stone/lateral stone rubble soling including hand packing with rubble chips etc complete(excluding cost of materials)		
560.00	Cmt	4	Supplying 80mm metal trap/granite/quartzite /gneiss/laterite stone metal at the for metal including conveying and stacking etc complete.		
560.00	Cmt	5	Spreading oversize 40mm/50mm/60mm/80mm metal including sectioning etc complete.		
280.00	Cmt	6	Supplying 60mm metal trap/granite/ quartzite/ gneiss/laterite stone metal at the road side for metal including conveying & stacking etc complete.		
280.00	Cmt	7	Spreading oversize 40mm/50mm/60mm/80mm metal including sectioning etc complete.		
560.00	Cmt	8	Supplying Hard murum/Kankar at the road side including conveying and stacking etc complete.		
560.00	Cmt	9	Spreading gravel/hard murum/soft murum & stone dust over the rubble soling oversize and size metal layer/blandage on W.B.M. surface etc complete.		
11200.00	Smt	10	Compacting sub grade gravel/oversize metal (200mm loose) layer 2 to 4 m wide with vibrotory roller including necessary labour materials and artificial watering etc complete.		
2800.00	Smt	11	Providing 50mm (about"2")thick semi grout bituminous road surface including supplying all materials preparing the existing road surface laying the required thickness of metal layer heating and spreading bitumen spreading chips laying with seal coat @ 125 Kg/100 square meter and compacting etc complete. (With Bulk asphalt 60/70 grade)		
71640.00	Smt	12	Providing and laying bituminous tack coat @ 50Kg/100m2 over B.T. surface.....by manual/mechanical sprayer including supplying all materials preparing the existing surface heating bitumen and applying tack coat evenly on the surface etc complete. (Using 60/70 grade)		

1791.00	Cmt	13	Providing and laying hot mix laid bituminous macadam 50/75 mm average thickness with... bitumen by weight of total mix for leveling course to remove irregularities/Base course including diversion of traffic supply of all material heating bitumen and chips in drum mix plant cleaning the road surface laying bibulous macadam by paver finisher including compaction transportation and cost of all materials bitumen from refinery etc complete (excluding tack coat)		
352820.00	Smt	14	Providing and laying Open graded permiz carpet 20mm thick with specified graded crushed aggregate fire wearing course including supplying all materials preparing and cleaning base loading of aggregates with front edge loader heating bitumen and aggregate in modern drum mix type of hot miz plant transportation the mix malarial from tipper and laying without paver without scada laying by manual means to required level and grade rolling with power rolling (Using Bulk Asphalt VG30 (60/70) grade)		
20.00	Hrs	15	Providing and supplying JCB Machine including diesel operator and cleaner and as directed by authority in charge.		
270.00	Rmt	16	Laying cement concrete pipe of IS 458-1988 Np 4 for MSH & NH Class in proper line level and slope including providing fixing collar in cement mortar 1:2 etc complete.		
1194.00	Smt	17	Providing and laying of hot applied thermoplastic compound 2.5mm thick Yellow/White including reflect rising glass beads @ 250gms per Sqm. Area thickness of 2.5mm is exclusive of surface applied glass beads as per IRS 35. The finished surface to be level uniform and free from streaks and holes etc complete with 3 years guarantee.		
				Total---	

Say Rs 2,82,04,681/- ONLY

Sd/xxx
City Engineer,
 Bhiwandi N.C.M. Corporation

Contractor's Name & Address :-

भिवंडी निजामपुर शहर महानगरपालिका, भिवंडी
बांधकाम विभाग, प्रभाग समिती क्रमांक ०३
ई- निवीदा सुचना क्रमांक ४६ सन २०१८-१९

भिवंडी निजामपुर शहर महानगरपालिकेच्या बांधकाम विभागात योग्य त्या वर्गातील नोंदणीकृत व अशा कामांच्या पूर्वनुभव असलेल्या कंत्राटदारांकडून खालील नमुद केलेले कामास बी-१ ई-निवीदा(ऑनलाईन) मागवित आहे.

अ.क्र.	कामाचे नांव	अंदाजपत्रकीय किंमत (रु.)	(ई.एम.डी.)इसा याची किंमत (रु.)	सुरक्षा अनामत रक्कम रोख(रु.)	विलातून (रु.)	कामाची मुदत (दिवस)	निवीदा पत्राची किंमत (रु.)	निवीदा पत्राचा प्रकार	नोंदणी वर्ग
१	प्र.क्र.४३ ब्रम्हानंदनगर येथे आर.सी.सी. तळ अधिक एक मजला ३२ सिट शौचालय तयार करणे.	४६,१९,४००/-	४६०००/-	९२,०००/-	९२,०००/-	१२० दिवस	१०२५/-	बी-१	वर्ग-५ व त्यावरील
२	प्र.क्र.३१ पद्मानगर यशवंत चाळ येथे ८ सिट सार्वजनिक शौचालय बांधणे.	९,९७,२१६/-	१०,०००/-	२०,०००/-	२०,०००/-	१२० दिवस	५२५/-	बी-१	वर्ग-६ व त्यावरील
३	प्र.क्र.३१ धामणकरनाका वॉटरवर्क्स कंपाउंड येथे प्रेमताई सुरेश पाटील सभागृहाच्या मागील बाजूस सी.सी.नाला बांधणे.	२४,६१,४८०/-	२५,०००/-	५०,०००/-	२५,०००/-	१२० दिवस	१०२५/-	बी-१	वर्ग-५ व त्यावरील
४	प्र.क्र.४५ कामतघर सॅ नं.१५८ पै.सर्व नं.७१,७२ व ७३ या परिसरांत मंजूर विकास आराखड्यानुसार रस्ते विकसित करणे.	२,८२,०४,६८१/-	१५००००/-	६,००,०००/-	६,००,०००/-	३६५ दिवस	२०२५/-	बी-२	वर्ग -३ व त्यावरील
५	प्र.क्र.३१ पद्मानगर सोसायटी चाळ येथे शौचालय बांधणे.	२३,९५,२७३/-	२४,०००/-	४८,०००/-	४८,०००/-	१२० दिवस	१०२५/-	बी-१	वर्ग -५ व त्यावरील
६	प्र.क्र.४५ जगन चौधरी घर ते महापौर याचे घरापर्यंत नाला बांधणे.	२५,००,०००/-	२५,०००/-	५०,०००/-	५०,०००/-	१२० दिवस	१०२५/-	बी-१	वर्ग -५ व त्यावरील